

ମା' ତାରିଣୀ ଠାକୁରାଣୀ ମନ୍ଦିର ଟ୍ରଷ୍ଟ

ସା/ସୋ.ଅ.- ଘଟଗାଁ, ଜି-କେନ୍ଦୁଝର-୭୫୮୦୨୭(ଓଡ଼ିଶା)

ଫୋନ୍-୦୬୭୩୩-୨୨୩୦୦୧



MAA TARINI THAKURANI TEMPLE TRUST

AT/P.O.- GHATGAON, DIST- KEONJHAR-758027(ODISHA)

PHONE-06733-223001

website- www.maatarini.co.in E-mail Id- maatarini.ghatgaon@gmail.com

ଚିଠି ନଂ. Letter No.: 664

ତାରିଖ Date: 22.11.19

QUOTATION CALL NOTICE


Sealed quotations are invited by the under signed from the registered supplier/contractor towards execute the following items for the work as below.

Name of the work:- Repair & Renovation of Yatri Nivas inside the premises Maa Tarini Temple, Ghatgaon (providing tiles to floor & wall tiles).

Sl.No.	Item of Materials	Qty	Unit	Est.Rate
1.	Dismantling & removing 2.5c.m. thick Artificial stone flooring including cost of all materials labour T&P etc. complete as per direction of Engineer-in-charge.	234.50 Sq.m.	Each Sqm	46.24
2.	Fixing tiles (Vetrified Tiles of size 600 mm x 600 mm) in floors treds or steps & landing on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing & polishing with cost, conveyance of all materials etc. complete as per direction of Engineer-in-charge.	234.50 Sq.m.	Each Sqm	1172.98
3.	Fixing tiles (ceramic) in floors treds or steps & landing on 25 mm thick bed of cement mortar 1:1 (1 cement: 1 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing & polishing with cost, conveyance of all materials etc. complete as per direction of Engineer-in-charge.	33.30 Sq.m.	Each Sqm	929.07
4.	Fixing tiles (ceramic) indadoo, skirting & rises of steps on 12 mm thick cement plaster in mortar 1:3 (1 cement:3 sand) jointed with neat cement slury mixed with pigment to rubbing & polishing with cost, conveyance of all materials etc. complete as per direction of Engineer-in-charge.	725.99 Sq.m.	Each Sqm	907.73
5.	Painting two coats with any approved paint on new/ old wood work including cost of primer all labour T&P etc. complete as per direction of Engineer-in-charge.	190.50 Sq.m.	Each Sqm	127.25
6.	Wall painting two coat with plastic emulsion paint over a coat of primer including cost of all labour T&P etc complete as per direction of Engineer-in-charge.	605.92 Sq.m.	Each Sqm	101.45

The quotation should reach in the office of the undersigned on or before dt...28.11.2019 in the office hour & the quotations shall be opened in the office of the undersigned at ...5 p.m... dt...28.11.2019... in presence of the quotationers or their authorized agents. The quotationers must have to produce their valid PAN/GSTIN/ Registration certificate and EMD Rs.65000/- (Sixty five thousand) only in shape of D.D. favoring "Maa Tarini Thakurani" alongwith the quotation. No quotations shall be received after the scheduled date & time.

The authority reserves the right to reject any or all the quotations without assigning any reasons thereof.


Executive Officer
Maa Tarini Thakurani Temple Trust
Ghatgaon, Keonjhar.